

Crestone — Installation Acceptance Checklist

Use this checklist end to end for every new Crestone installation with an SAP source. Don't mark a section done just because the UI loaded or the installer showed a success message.

Start here: define the SAP source

Ask the client which kind of SAP source they'll extract from before requesting anything else — it decides which network and SAP-side requirements apply. SAP ABAP (ECC, S/4HANA on-premise, RISE: tables, reports, BAPIs, CDC) connects via RFC through the SAP microservice → section 4.1. SAP OData (Gateway services, extractors/ODP) connects via HTTPS straight to the OData service → section 4.2. Extractors (2LIS_*, ODP) must go through OData, not RFC: since June 2026 SAP blocks ODP-RFC for external systems (SAP Note 3255746). If the client uses both kinds of source, complete 4.1 and 4.2. SAP BW connects over RFC like ABAP (4.1 plus the extra BW authorizations); Business One and ByDesign are OData-based (4.2); SAP HANA (direct database connection) isn't covered by this checklist yet.

- ☐ SAP source confirmed with the client (ABAP, OData, or both), and which objects will be extracted
Seidor / client

1. Before installing

- ☐ Server meets the minimums (230 GB disk, 16 GB RAM, 8 CPU cores, 4 GB swap), x86_64 architecture
Client infrastructure
- ☐ Ports 80/443/81/7000/22 enabled as needed (see Minimum Technical Requirements)
Client network team
- ☐ Outbound TCP/587 to email-smtp.us-east-1.amazonaws.com (AWS SES) enabled — it's the only outbound port in the whole block; if missing there's no visible error, the confirmation email just never goes out
Client network team
- ☐ If the install starts with just an IP (no custom DNS yet), access is over HTTP, not HTTPS — confirm the client's security policy/proxy doesn't block plain HTTP before assuming “the UI won't load”
Client network team
- ☐ Allowed domains: *.s3.amazonaws.com (always), plus Docker/Ubuntu ones if the server doesn't already have them
Client network team
- ☐ Root/sudo access confirmed on the server
Client infrastructure
- ☐ Decided whether to use the default nip.io hostname or a custom DNS from the start (see the risk of it being blocked by filters like FortiGuard)
Seidor / client
- ☐ If the source is SAP ABAP: client's sysnr confirmed, and the network scenario defined (direct access / VPN / SAProuter)
Seidor / Basis
- ☐ If the source is SAP OData: the service's base URL (host and HTTPS port) defined and reachable from the Crestone server
Seidor / Basis

2. Install Crestone

- ☐ install.sh ran without errors and shows the success message
Seidor

- ☐ All containers are Up and healthy (docker compose ps), none stuck in Restarting/Exited
Seidor
- ☐ housekeeping.sh run after installing, to free up the space used by duplicated images
Seidor
- ☐ UI reachable from the configured hostname (nip.io or custom DNS) from the client's normal network, not only from a technical network/VPN
Seidor · confirm with the client

3. Crestone users and licensing

- ☐ License activated (online with a code, or offline with a signed file), limits and expiration matching what was contracted
Seidor
- ☐ noreply@notifications.crestone.io allowlisted on the company's mail gateway/firewall (once, for everyone)
Client network team
- ☐ Also allowlisted on each invited user's own mailbox rules (M365/Google Workspace can apply different filtering per person or group)
The user / their IT
- ☐ Crestone user created, confirmation email arrived
Seidor · verify with a real signup, don't assume
- ☐ The confirmation link opens and works from the user's normal network, without needing a VPN
Seidor
- ☐ If the client configured their own SMTP (Settings → SMTP instead of Crestone's default): the test send passed
Seidor (optional, if applicable)
- ☐ MFA configured if the client's security policy requires it
Client

4. SAP source

Complete 4.1, 4.2, or both, according to the source defined at the start.

4.1 SAP ABAP — role, user, and RFC connection

- ☐ Transport requests (OTs) imported into SAP without errors
Basis
- ☐ Technical user created (Communication or Dialog type)
Basis
- ☐ ZCRESTONE role imported, assigned to the user, and user comparison run
Basis
- ☐ User has S_RFC, RFC_SYSTEM_INFO, and access to the tables/extractors in scope
Basis / Security
- ☐ Port 32NN open from Crestone to the application server
Client network team
- ☐ The SAP host's FQDN resolves via DNS from the VM and from the container (not enough for the IP alone to respond over TCP)
Basis / Client network team

CRESTONE — INSTALLATION ACCEPTANCE CHECKLIST

- ☐ Port 33NN open from Crestone to the SAP gateway
Client network team · the most commonly forgotten one
- ☐ If there's a SAProuter: saproustab allows both destinations, dispatcher and gateway
SAProuter administrator
- ☐ reginfo and secinfo authorize CRESTONE_SERVER and the CRES_SLOT_*
Basis
- ☐ Gateway ACLs reloaded after editing the files
Basis
- ☐ Type-T RFC destination created in SM59 and its connection test passes
Basis
- ☐ The connection's Gateway Host field points to the client's real SAP host, not a Crestone/demo server
Seidor · confirm against the real ashost
- ☐ If parallelism will be used: the number of CRES_SLOT_N created in SAP matches what's configured in Settings → Parallel Extraction
Seidor / Basis

4.2 SAP OData — what to request from the client

OData sources don't use the RFC layer, so the transport requests, the ZCRESTONE role, and the RFC connection (Steps 2–5 of the setup guide) don't apply — go straight to the connection in Step 6.

- ☐ OData service(s) published and active in the SAP Gateway (/IWFND/MAINT_SERVICE); for extractors, OData services built on ODP
Basis
- ☐ Service base URL confirmed (without the service name — the service is chosen later, on the node)
Basis
- ☐ Authentication method agreed: Basic Auth or API Key
Basis / client
- ☐ Technical user with authorization to run the services (typically S_SERVICE) and access to the data each service exposes
Basis / Security
- ☐ HTTPS port of the SAP server (ICM / Web Dispatcher) open from Crestone
Client network team
- ☐ OData source connection test passes
Seidor
- ☐ If the services are extractors/ODP: node timeout set generously (the first page can take several minutes; real tests needed 30+ minutes)
Seidor

5. Connections in Crestone (source and destination)

- ☐ Source connection created in Crestone and its connection test passes
Seidor
- ☐ Destination connection created in Crestone and its connection test passes
Seidor

- ☐ If the destination is cloud-based (Azure/AWS/GCP/Snowflake/Databricks/etc.): that connector's domains confirmed with the client and allowed on their outbound internet access
Client network team

6. Test node, job, and extraction

- ☐ Test node created using the configured source connection
Seidor
- ☐ Node preview returns data
Seidor
- ☐ If the table/extraction is large: filters or Batch by Field were applied before running an unbounded Full
Seidor
- ☐ Test job defined and executed
Seidor
- ☐ The full extraction (not just the preview) completes successfully and the data reaches the destination
Seidor · validate both, not just the preview
- ☐ Data in the destination validated against a known sample
Client validates

7. Monitor

- ☐ The test execution shows up in Monitor → Performance/History with a successful status
Seidor
- ☐ No errors in Monitor → Logs (UI / Engine / SAP tabs) tied to the execution
Seidor
- ☐ If cancelling an execution was tested: Cancel execution works and leaves no residual processes on the SAP side
Seidor (optional, if applicable)

8. Closing

- ☐ No item on this list was marked “done” just because the UI loaded or the installer showed 11/11
Seidor
- ☐ Evidence kept: rows extracted, duration, screenshots of the key screens (no visible credentials/secrets)
Seidor